#### (12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

# (19) World Intellectual Property Organization International Bureau



# 

(43) International Publication Date 20 September 2001 (20.09.2001)

**PCT** 

(10) International Publication Number WO 01/68929 A1

(51) International Patent Classification?: C22C 38/08, 38/18, 38/20, 38/22, 38/28, 38/38, 38/40, 38/42, 38/44, 38/50, 38/58

(21) International Application Number: PCT/US01/07525

(22) International Filing Date: 8 March 2001 (08.03.2001)

(25) Filing Language:

English

(26) Publication Language:

English

(30) Priority Data: 60/189,669

15 March 2000 (15.03.2000) US

(71) Applicant (for all designated States except US): INCO ALLOYS INTERNATIONAL, INC. [US/US]; 3200 Riverside Drive, Huntington, WV 25705 (US).

(72) Inventors; and

(75) Inventors/Applicants (for US only): CRUM, James, R. [US/US]; 20 Quail Drive, Ona, WV 25545 (US). SUAREZ, Francis, S. [US/US]; 608 Shivel Lane, Huntington, WV

25705 (US). MANNAN, Sarwan, K. [US/US]; 1 Orchard Hill Road, Barboursville, WV 25504 (US). HARTMANN, Vernon, W. [US/US]; 12 Morris Court, Culloden, WV 25510 (US).

- (74) Agents: BYRNE, Richard, L. et al.; Webb Ziesenheim Logsdon Orkin & Hanson, P.C., 700 Koppers Building, 436 Seventh Avenue, Pittsburgh, PA 15219-1818 (US).
- (81) Designated States (national): CA, JP, US.
- (84) Designated States (regional): European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR).

#### Published:


- with international search report
- before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: CORROSION RESISTANT AUSTENITIC ALLOY

# Sigma Solvus, Temperature °F

22 Nickel 20.5Cr, Mo, N, Balance Fe



(57) Abstract: An austenitic alloy having improved ductility/processability and improved pitting and crevice corrosion resistance comprising, in % by weight, about: 25-30 % Ni; 19-23 % Cr; 6-8 % Mo; 0.3-0.5 % N; 0.5 % Mn; 0-1.5 % Cu; 0-0.2 % C; 0-1 % Al; 0-0.01 % S; 0-1 % Ti; 0-1 % Si; up to trace amounts of Mg, Ca, and Ce; and balance Fe plus incidental impurities.

11/68979 A

10

15

20

25

30

# 

#### 1. Field of the Invention

The present invention relates to nickel-iron-chromium alloys containing molybdenum for the purpose of providing resistance to pitting and crevice corrosion.

#### 2. Discussion of the Related Art

Certain ferrous alloys including INCOLOY® alloy 25-6MO (hereinafter referred to as "alloy 25-6MO") are particularly useful for their exceptional resistance to many corrosive environments. INCOLOY® is a trademark of the Special Metals group of companies. Alloy 25-6MO nominally contains by weight percent 25 nickel, 20 chromium, and 6 molybdenum. Examples of such corrosion resistant alloys are disclosed in U.S. Patent No. 4,545,826 as containing by weight percent 20-40 nickel, 14-21 chromium, 6-12 molybdenum, maximum of 2 manganese, and 0.15-0.30 nitrogen. These alloys are annealed at relatively high temperatures, namely, over 2100°F (1149°C), typically about 2200°F (1204°C).

These nickel-chromium-molybdenum alloys are particularly suited for use in chemical and food processing, pulp and paper bleaching plants, marine and offshore platforms, salt plant evaporators, air pollution control systems, and various equipment for the power industry. These are aggressive aqueous environments which contain halides. Accordingly, the alloys formed into components of such systems must have good resistance to pitting and crevice corrosion. In addition, the alloys must have good processability since they are fabricated into a variety of intricate forms. Processability includes well-known hot forming techniques such as forging and rolling or other forming operations such as drawing and bending to mention a few. However, it is difficult to produce a nickel-chromium-molybdenum alloy with good processability because high concentrations of Mo, Cr and N which provide pitting resistance are also known to be detrimental to the processability of the alloy.

Accordingly, a need remains for a nickel-chromium-molybdenum alloy having improved corrosion resistance as well as improved processability.

#### SUMMARY OF THE INVENTION

This need is met by the nickel-iron-chromium alloy of the present invention which most preferably includes about the following ranges by weight percent:

ELEMENT	WEIGHT PERCENT, (wt.%)
Ni	26 - 29
Cr	20 - 22
Mo	6.5 - 7.5
Mn	0 - 5
Cu	0 - 1
N	0.3 - 0.5
Fe	Balance

5

10

15

Heats of the alloys of the present invention containing nitrogen in the amount of about slightly greater than 0.3 wt.% to 0.4 wt.% exhibit significantly improved pitting resistance and exhibit improved crevice corrosion resistance over prior Ni-Cr-Mo alloys. Presently preferred lower limits for N are 0.31 wt.% and 0.33 wt.%. The alloys of the present invention also provide additional improved properties, such as: (1) at least 100°F (38°C) lower sigma solvus temperatures so as to decrease the propensity to form sigma phases during processing, (2) higher yield strength and good ductility, (3) allows the use of relatively low temperature annealing steps, namely, less than 2100°F (1149°C), and, hence, improved processability for forming various shaped components.

#### BRIEF DESCRIPTION OF THE DRAWINGS

Fig. 1 is a graph of sigma solvus temperature contour lines at 22 wt.%

Fig. 2 is a graph of sigma solvus temperature contour lines at 25 wt.%

20 nickel;

nickel;

nickel;

Fig. 3 is a graph of sigma solvus temperature contour lines at 27 wt.%

Fig. 4 is a graph of PREN contour lines at 22-27 wt.% nickel;

10

Fig. 5 is a graph of the comparison of the effects of molybdenum and nitrogen on both sigma solvus temperature and PREN calculations; and

Fig. 6 is a comparison of PREN and sigma solvus temperatures for a composition of the present invention and prior art alloys.

# DESCRIPTION OF THE PREFERRED EMBODIMENTS

The present invention is an improvement over INCOLOY® alloy 25-6MO which exhibits improved pitting and crevice corrosion resistance as compared to prior Ni-Cr-Mo alloys. These improvements are believed to be the result of the inclusion of about 6.5-7.5 wt.% Mo and about 0.33-0.40 wt.% N to a corrosion resistant alloy such as INCOLOY® alloy 25-6MO.

In particular, the alloy of the present invention contains the elements set forth in Table 1 by weight percent of the alloy in about the following ranges:

	Table 1	<del></del>	<del></del>	
ELEMENT	<b>第20 年 18 22 6</b> 24	WEIGHT	PERCENT	THE WAY
	Broad	Medium	Narrow	Nominal
Ni	25-30	26-29	26-28	27
Cr	19-23	20-22	20-21.5	21
Мо	6-8	6.5-7.5	6.6-7.5	7
N	0.3-0.5	0.31-0.35	0.33-0.4	0.35
Mn	0-5	0-5	.5-1.5	1.0
Cu	0-1.5	0-1	0.7-1.0	0.8
C	0-0.2	0.01-0.2	0.01-0.02	< 0.02
Al	0-1	0.01-0.15	0.05-0.15	0.1.
S	0-0.01	0-0.002	< 0.002	< 0.001
Ti	0-1	0-1	0-0.03	< 0.03
Si	0-1	0.1	0.5	< 0.5
Mg	<0.1			
Ca	<0.1			
Ce	<0.1			
Fe and Incidental Impurities	Balance	Balance	Balance	Balance

The alloy of the present invention may further contain up to 0.5 wt.% V.

A particularly preferred alloy of the present invention includes by weight percent about 27 Ni, 21 Cr, 7.2 Mo, 1.0 Mn, 0.8 Cu, and 0.33 N. The present invention is a result of both theoretical calculations and physical testing of alloys containing molybdenum for corrosive environments.

20

10

15

20

25

30

Certain theoretical calculations are known techniques for evaluating a potential alloy. These calculations include sigma solvus temperature and pitting resistance equivalent number (PREN) which is a numerical estimate of the pitting resistance based on the alloy composition where PREN equals %Cr + 3.3 (%Mo) + 30(%N). A high sigma solvus temperature in 6MO alloys (alloys containing about 6 wt.% molybdenum) has been known to result in poor metallurgical stability and excessive processing problems. One goal during development of the present invention was to define an alloy composition having the best possible combination of a high PREN for improved pitting resistance as well as a low sigma solvus temperature for stability and improved processing of the alloy. Calculations of sigma solvus temperatures and PREN numbers were made for a factorial design encompassing Ni at 22, 25 and 27 weight percent, Mo at 6.0, 6.5 and 7.0 weight percent, and N at 0.20, 0.28 and 0.35 weight percent with 20.5 Cr and the balance Fe. The calculated effect of Mo and N content on the sigma solvus temperatures in 22 Ni, 25 Ni and 27 Ni compositions are shown in Figs. 1-3. The contour lines in Figs. 1-3 are drawn to show various sigma solvus temperature levels. Figs. 1-3 demonstrate that the higher contents of nickel and nitrogen decrease the sigma solvus temperature whereas increases in the amount of molybdenum increase the sigma solvus temperature. Fig. 4 presents contour lines for PREN values over a range of 6-7 wt.% Mo and 0.2-0.35 wt.% N in an alloy with 22-27 wt.% Ni and 20.5 wt.% Cr. Fig. 4 demonstrates that higher molybdenum and nitrogen levels lead to higher PREN numbers. Based on these calculated PREN values, the higher the molybdenum and nitrogen levels, the greater the resistance to pitting is expected. However, nitrogen was already shown in Figs. 1-3 to decrease the sigma solvus temperature, whereas molybdenum increases the sigma solvus temperature.

Hence, in the present invention, a balance was struck between these two desired goals. The desired lower sigma solvus temperatures dictate using a higher nitrogen content and lower molybdenum content while the desired PREN values suggest using higher molybdenum and nitrogen levels. This is shown graphically in Fig. 5 where the PREN contour lines are superimposed on the sigma solvus contour lines produced in Figs. 1-4 for 27 Ni-20.5 Cr compositions. It was determined that the best combination of a relatively low sigma solvus temperature of

10

15

about 1900°F and an acceptable PREN level of about 54 was obtainable at a nitrogen level of about 0.35%. This is noted by the data point with an "\*" for a 27-7 composition (27Ni, 20.5Cr, 7Mo and 0.35N). This 27Ni-20.5Cr-7Mo-0.35N composition was shown to have significantly higher PREN and lower sigma solvus temperatures than commercially available alloys. The common compositions of several commercial 6MO type alloys are set forth in Table 2.

	Table 2 Composition of Common 6MO Type Alloys							
Element 25-6MO 6XN 254SMO 654SMO								
Ni	25	24	18	22				
Cr	20.5	21	20	24				
Mo	6.7	6.5	6.1	7.3				
N	0.20	.22	.22	0.5				
Mn	0.7		0.6	3				
Cu	0.9		0.7	0.5				
σ Solvus	2036°F (1113°C)	2079°F (1137°C)	2102°F (1149°C)	2179°F (1193°C)				
PREN	48.0	49.0	46.4	63.1				

Theoretical calculations show that 27Ni-20.5Cr-7Mo-0.35N composition has significantly lower sigma solvus temperature and higher PREN number than most of the conventional alloys, Fig. 6. Although alloy 654SMO has a very high PREN number, it also has a very high sigma solvus temperature, which corresponds with more difficult processing and product limitations and, hence, is less acceptable than the alloy of the present invention. The experimental sigma solvus temperature for a 27Ni-20.5Cr-7Mo-0.35N composition was marginally higher than the theoretical prediction.

It is believed that the molybdenum content can be about 6.5-7.5 wt.% and the nitrogen content can be about 0.33-0.40 wt.% to exhibit the desired balance of properties. Accordingly, the present invention lies in the use of about 6.5-7.5 wt.% Mo and about 0.33-0.40 wt.% N in a nickel-chromium alloy.

Although the invention has been described generally above, the following particular examples give additional illustrations of the product and process steps typical of the present invention.

## **EXAMPLE 1**

Laboratory sized heats (50 lbs.) were produced by both air and vacuum melting. The amount of deoxidizing elements, other residuals and the hot rolling practice were varied as set forth in Table 3.

Ingots were rolled to 2.25 inch square, 0.250 inch flat, 0.125 inch strip and/or 5/8 inch rod. Chemical analyses were conducted on ladle samples and/or final products. Critical pitting temperature and crevice corrosion temperature (the lowest temperatures at which attack occurs) were both conducted according to ASTM G48, Practices C and D on annealed specimens with a 120 grit ground surface.

VSDOCID: <WO\_\_\_\_0168929A1\_I\_>

_		100	т—		т	<del></del>				
		Process	Но	Но,Ма	Но,Ма	Но,Ма	Но,Ма	Но,Ма	Но,Ма	
		Sample	Ld Sq	Ld Plate	Ld Plate	Ld Plate	Ld Plate	Ld Plate	Ld Plate	Plate
		Z	.36	.35	.34	.35	.35	.33	.34	.20
		ဦ	.000	.002	.001	.005	900.	.003	.002	1
		Ca	<.001	.003	.002	<.001	<.001	.002	.003	i
		Mg	<.001	.013	.010	.016	.012	.002	.003	1
	ons	, Wo	6.59	7.23	6.64	7.28	7.48	7.17	7.17	6.79
ι.	Experimental Compositions	Ţ,	.02	.02	.01	.02	.02	.02	.02	00.
Table 3	mental C	W	.01	.01	.01	.05	.05	.01	10.	.11
	Experi	j. Č	20.61	21.19	20.73	21.06	21.03	21.05	21.07	20.01
		Ź	26.00	27.76	25.91	28.22	27.96	27.11	27.11	25.93
		Cu 🤝	.05	.05	.05	.73	.15	.21	.21	.85
		. Si	.45	.47	.45	.43	.42	.44	.44	.34
		S	.005	.005	.003	.004	.005	.004	.004	.002
		υ Σ	65.	09.	.59	.55	1.94	.64	.57	1.93
		ပ	.010	010.	.012	.018	.015	910	.018	.048
		Heat	HV9240*	HV9242A	HV9244A	HV9438	HV9439	HV9440	HV9441	HV9117A**

Did not roll to plate, cut samples out of cracked 2.5" squares.
\*\* Comparative Example
Ho = homogenize, Ma = machine ingot, Ld = ladle analysis, Sq = 2.5" square analysis

10

15

20

25

30

## **COMPARATIVE EXAMPLE**

A 50 lb. laboratory heat of an alloy having less nitrogen than that of the present invention was produced and also appears in Table 3 as Heat HV9117A.

Results of the critical pitting temperature (CPT) and critical crevice corrosion temperatures (CCT) tests conducted on plate samples of certain of the alloys set forth in Table 3 are reproduced in Tables 4 and 5.

The data set forth in Tables 4 and 5 demonstrates that both pitting resistance and crevice corrosion resistance improve with increasing amounts of Mo and N. The typical CPT and CCT temperatures for conventional 25-6MO alloys are 158°CF (70°C) and 95°F (35°C), respectively. Upon slightly increasing the Mo, as was done in Heat HV9117A of the Comparative Example, the CPT and CCT values were increased to 176°CF (80°C) and 104°F (40°C), respectively. However, further increases in the amount of Mo and N in Heat HV9242A (an alloy of the present invention) increased the CPT and CCT values to 195°F (85°C) and 140°F (60°C), respectively. Hence, higher Mo and N levels are believed to be beneficial.

An autogenous gas tungsten arc welding (GTAW) test was conducted in the flat position on 0.062" thick sheet rolled from Heat HV9438 and others to evaluate tungsten deterioration and molten metal fluid flow. Visual examination of the tungsten after welding did not illustrate excessive deterioration or spalling. Weldbead profile and geometry were not adversely affected by the 0.35 percent addition of nitrogen. In addition, the fluidity and wetting characteristics of the molten metal were not significantly degraded by the nitrogen additions.

The mechanical properties of the alloys of the present invention were also tested. The effect of annealing on room temperature tensile properties was tested for Heat HV9242A. INCOLOY® alloy 25-6MO generally is required to have a minimum 0.2% yield strength of 43 Ksi and a minimum elongation of 40%. To obtain these properties, it has been previously necessary to use a relatively high annealing temperature of 2200°F (1204°C) to obtain the desired ductility. Nevertheless, the strength at this ductility is often only marginally better than 43 Ksi. Table 6 presents the impact on room temperature properties of annealing temperatures from 2050°F to 2150°F on 0.125" strip formed from heat HV9242A after cold rolling to 50%. Table 7 presents the results of testing the same heat HV9242A as 0.150"

10

15

20

strip after cold rolling to 50% when annealed at temperatures of 1800°F to 2200°F as compared to commercial heat of 25-6MO.

The data shows that higher yield strength and elongation are obtained for the new alloy as compared to 25-6MO throughout the annealing temperature range. It is believed that the higher nickel or lower sigma solvus temperature contributes to the improved ductility whereas the higher molybdenum and nitrogen content provide the high strength for the alloy. Alloy 25-6MO has a high sigma solvus temperature that requires a high annealing temperature of 2200°F (1204°C). The alloy of the present invention may be annealed at reduced temperatures compared to conventional alloy 25-6MO which also results in increased strength.

Thus, the alloy according to the present invention, with the combination of both a high PREN number ("pitting resistance equivalent number") and a low sigma solvus temperature, provides superior corrosion resistance with the added advantage of easier processing. A low sigma solvus temperature allows hot rolling or forming operations with less danger of precipitating deleterious sigma phase. Also, final annealing can be performed at a lower temperature than materials which are more prone to sigma phase and require a higher solution annealing temperature to remove unwanted precipitation. Lower processing and annealing temperatures reduce unwanted oxidation, lower energy costs and provide a higher strength, fine grain size final product.

	Table 4 Critical Pitting Temperature Test Results in ASTM G48, C 0.250° Plate, HR + 2200°F/½hr. WQ						
Heat No.   Composition   Test Temperature °C   Max. Pit Depth., mils							
HV9117A	26Ni-20Cr-6.8Mo20N	70	0				
n	11	75	0				
11	п	80	5				
11	11	85	5				
HV9242A	28Ni-21Cr-7.2Mo35N	70	0				
11	11	75	0				
"	11	80	0				
- 11	. 11	85	11				
HV9244A	26Ni-20.7Cr-6.6Mo34N	70	0				
11	11	75	0				
11	11	80	20				
"	11	85	5				

Summary:

HV9117A CPT = 80°C

HV9242A CPT = 85°C HV9244A CPT = 80°C

		Table 5	<del></del>	<del></del>
	Critical Crevice Temp		s in ASTM G48 D	
	0.250" Pla	te, HR + 2200°F/½	hr. WO	
Heat No.	Composition	Test	Max. Crevice Attack	% Crevices
		Temperature, °C	Depth, mils	Attacked
HV9117A	26Ni-20Cr-6.8Mo20N	35	0	0
н	11	40	3	13
11	11	40	0	0
11	п	45	35	50
н	11	45	23	50
HV9242A	28Ni-21Cr-7.2Mo35N	35	0	0
н	ir .	40	0	0
11	n	45	0	0
tt	pt	50	0	0
11	19	55	0	0
11	**	60	85	100
HV9244A	26Ni-20.7Cr-6.6Mo34N	40	0	0
**	n e	40	0	0
11	"	45	3	8
"	"	45	0	0
11	11	50	1	4
11	"	50	1	4
11	11	55	4	33
11	11	55	9	50

Summary:

5

HV9117A CCT = 40°C

HV9242A CCT = 60°C

HV9244A CCT = 45°C

			_,	,			
				Hardness Rb	87	98	06
	roperties	-		. Elongation	47.4	48.3	48.7
	Temperature Tensile P	Cr-7.2Mo-0.35N	• + Anneal	Tensile Strength Ksi	122.7	120.8	119.7
Table 6	Effect of Annealing Temperature on Room Temperature Tensile Properties	Heat HV9242A: 28Ni-21Cr-7.2Mo-0.35N	0.125" Strip, Cr 50% + Anneai	0.2% Yield Strength Ksi Tensile Strength Ksi Elongation   Hardness Rb	56.9	61.0	54.6
	Effect of Anne	•		Annealing Temperature	2050°F (1121°C)/1/4 h, WQ	2100°F (1149°C)/1/4 h, WQ	2150°F (1177°C)/1/4 h, WQ

_			s, FIRb	25-6MO	97	94	91	88	95*	84	84	81
	pa		Hardness, HRb	HV9242A	66	97	96	. 93	93*	94	92	87
	Effect of Annealing Temperature on RTT Properties, Strip CR 50% + Anneal as Indicated Exp. 4022 HV9242A, Strip 0.150", Test Drawing No. CR-15	lo. T-9A	ongation	25-6MO	31.69	37.5	37.3	40.0	45.2	43.8	42.0	42.2
	Strip CR 50% + At Drawing No. C.	" Test Drawing N	% Elon	HV9242A	32.0	39.6	41.9	44.0	45.2*	48.5	50.0	50.4
Table 7	RTT Properties, Strip 0.150", Tes	p Z9237P, 0.063	Ksi	25-6MO	126.2	119.3	118.8	113.6	102.5	107.8	8.86	96.4
	aling Temperature on RTT Properties, Strip CR 50% + Anne. Exp. 4022 HV9242A, Strip 0.150", Test Drawing No. CR-15	Commercial 25-6MO Strip Z9237P, 0.063" Test Drawing No. T-9A	ULT Ksi	HV9242A	132.7	129.9	131.2	128.5	129.0*	125.5	122.3	119.2
	fect of Annealing Exp.	Commer	0.2% Y.S., Ksi	25-6MO	65.7	59.4	59.0	55.5	46.3	47.7	43.1	41.3
	Ef		0.2%	HV9242A	69.2	0.99	66.1	60.5	63.8*	60.3	54.2	57.3
			Annealing Temp./	% b, AC	1800°F (982°C)	1900°F (1038°C)	1925°F (1052°C)	1950°F (1066°C)	1975°F (1079°C)	2000°F (1093°C)	2100°F (1149°C)	2200°F (1204°C)

\* Average of duplicate test

JSDOCID: <WO\_\_\_\_0168929A1\_I\_>

While specific embodiments of the invention have been described in detail, it will be appreciated by those skilled in the art that various modifications and alternatives to those details could be developed in light of the overall teachings of the disclosure. The presently preferred embodiments described herein are meant to be illustrative only and not limiting as to the scope of the invention which is to be given the full breadth of the appended claims and any and all equivalents thereof.

SDOCID: <WO\_\_\_\_0168929A1\_I\_>

WE CLAIM:

1. A corrosion resistant austenitic alloy consisting essentially of, in % by weight, about:

Ni: 25-30

5 Cr: 19-23

Mo: 6-8

N: 0.3-0.5

Mn: 0-5

- Cu: 0-1.5

10 C: 0-0.2

Al: 0-1

S: 0-0.01

Ti: 0-1

Si: 0-1

Mg: up to trace amounts

Ca: up to trace amounts

Ce: up to trace amounts

Fe: balance including incidental impurities.

- 20 2. The alloy of claim 1 having a sigma solvus temperature of less than 2100°F and a pitting resistance equivalent number PREN of at least 50, wherein:

  PREN = %Cr + 3.3(%Mo) +30%N.
- 3. The alloy of claim 1, including about 26-29% Ni; 20-22% Cr; 25 6.5-7.5% Mo and 0.33-0.45% N.
  - 4. The alloy of claim 1, including about 26-28% Ni; 20-21.5% Cr; 6.6-7.5% Mo and 0.33-0.4% N.
- 5. The alloy of claim 1, including about 27% Ni; 21% Cr; 7% Mo;0.35% N; 1.0 Mn and about 0.8 Cu.

6. A corrosion resistant austenitic alloy consisting essentially of, in % by weight, about:

Ni: 26-29

Cr: 20-22

5 Mo: 6.5-7.5

N: 0.31-0.45

Mn: 0-5

Cu: 0-1

C: 0-0.2

10 Al: 0-1

S: 0-0.01

Ti: 0-1

Si: 0-1

Mg: up to trace amounts

15 Ca: up to trace amounts

Ce: up to trace amounts

Fe: balance plus incidental impurities

7. The alloy of claim 6 having a sigma solvus temperature of less

than about 2000°F and having a pitting resistance equivalence number (PREN) of greater than about 54, wherein:

PREN = %Cr + 3.3(%Mo) + 30(%N).

8. A corrosion resistant austenitic alloy consisting essentially of in

25 % by weight about:

Ni: 26-28

Cr: 20-21.25

Mo: 6.6-7.5

N: 0.33-0.4

30 Mn: 0-5

Cu: 0-1

Al: 0-1

10

S: 0-0.01 Ti: 0-1

Si: 0-1

Mg: up to trace amounts

Ca: up to trace amounts

Ce: up to trace amounts

Fe: balance plus incidental impurities.

9. The alloy of claim 8 having a sigma solvus temperature of less than about 2000°F and having a pitting resistance equivalence number (PREN) of greater than about 54, wherein:

PREN = %Cr + 3.3(%Mo) + 30(%N).

10. A corrosion resistant austenitic alloy having a nominal composition consisting essentially of, in % by weight, about:

15 Ni: 27

Cr: 21

Mo: 7

N: 0.35

Mn: 0.6

20 Cu: 0.2

Al: 0-1

S: 0-0.01

Ti: 0-1

Si: 0-1

25 Mg: up to trace amounts

Ca: up to trace amounts

Ce: up to trace amounts

Fe: balance plus incidental impurities.

30 11. The alloy of claim 10 having a sigma solvus temperature of about 1900°F or less and having a pitting resistance equivalence number (PREN) of about 54 or greater, wherein:


-17-

PREN = %Cr + 3.3(%Mo) + 30(%N).


The alloy of claim 10 having a critical pitting temperature
 (CPT) of greater than 80°C and a critical crevice corrosion temperature (CCT) of
 greater than 50°C.

SDOCID: <WO\_\_\_\_\_0168929A1\_I\_>


Sigma Solvus, Temperature °F Figure 1




Sigma Solvus, Temperature °F Figure 2




Sigma Solvus, Temperature °F Figure 3












Comparison of the Effects of Molybdenum and Nitrogen on Sigma Solvus Temperature and PREN Calculations 27 Ni, 20.5Cr, Mo, N, Balance Fe Figure 5







ISDOCID: <WO\_\_\_\_\_0168929A1\_I\_:

#### INTERNATIONAL SEARCH REPORT

International application No. PCT/US01/07525

A. CLAS	SSIFICATION OF SUBJECT MATTER					
	Please See Extra Sheet.	مينجه	recognition —			
	: 148/325, 327;420/34, 43, 52, 94, 96, 97 o International Patent Classification (IPC) or to both r	national classification and IPC				
	DS SEARCHED					
	ocumentation searched (classification system followed	by classification symbols)				
U.S. :	148/325, 327;420/34, 43, 52, 94, 96, 97	-				
0.5.	0.0 140/323, 32/3420/34, 43, 32, 34, 30, 37					
Documentat	ion searched other than minimum documentation to the	extent that such documents are included	in the fields searched			
Electronic d	Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)					
USPAT,	USPGPUB, EPO abstracts, JPO abstracts, Derwent					
C POC	LIMENTS CONCIDENTS TO BE DELEVING					
C. DOC	UMENTS CONSIDERED TO BE RELEVANT	·				
Category*	Citation of document, with indication, where app	propriate, of the relevant passages	Relevant to claim No.			
Y	US 5,945,067 (HIBNER et al) 31 Aug	ust 1999, all of document.	1-12			
		·	}			
Y	US 5,141,705 (STENVALL et al) 25 A	August 1992, col 3 lines 19-	1-12			
·	23, col 4 lines 4-36, col 5, lines 32-42					
			l			
Y	US 4,981,646 (CULLING) 1 January 1	991, col 6 lines 21-29, col 7	1-12			
	lines 9-13.					
	770 4 000 544 57777 4					
Y	US 4,883,544 (UEDA et al) 28 Noven	aber 1989, col 8, line 63-col	1-12			
	9, line 2.					
	110 4 545 006 (MaCHININ at al) 9 Oats	show 1005 all of document	1 1 1 2			
A	US 4,545,826 (McCUNN et al) 8 Octo	ober 1985, all of document.	1-12			
A	US 5,841,046 (RHODES et al) 24 Nove	ember 1008 all of document	1-12			
The state of the s		ciniber 1998, an or document.	1-12			
,						
X Furth	ner documents are listed in the continuation of Box C.	See patent family annex.				
-	ecial categories of cited documents; cument defining the general state of the art which is not considered	later document published after the interest date and not in conflict with the applic	ation but cited to understand the			
· to	be of particular relevance	principle or theory underlying the inv				
	riier document published on or after the international filing date	"X" document of particular relevance; the considered novel or cannot be considered when the document is taken alone	red to involve an inventive step			
cit	cument which may throw doubts on priority claim(s) or which is ted to establish the publication date of another citation or other		se algiment insugation consent t			
	ectal reason (as specified) cument referring to an oral disclosure, use, exhibition or other means	considered to involve an inventive	step when the document is			
	cument published prior to the international filing date but later than	combined with one or more other suc being obvious to a person skilled in	the art			
	the priority date claimed "&" document member of the same patent family					
Date of the	actual completion of the international search	Date of mailing of the international se	arch report			
23 MAY	2001	17 JU	2001			
Name and	mailing address of the ISA/US	Authorized officer	LCUUI			
Commissio	oner of Patents and Trademarks		Ιγν"			
Box PCT Washington	n, D.C. 20231		BORAH THOMAS ( ) LEGAL SPECIALIST			
Facsimile N	No. (703) 305-3230	Telephone No. (703) 308-1146	u.uni, di Loinide			

Form PCT/ISA/210 (second sheet) (July 1998)\*

NSDOCID: <WO\_\_\_\_0168929A1\_I\_>

## INTERNATIONAL SEARCH REPORT

International application No.
PCT/US01/07525

C (Continuation). DOCUMENTS CONSIDERED TO BE RELEVANT						
Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No				
A	US 5,169,266 (SALA et al) 8 December 1992, all of document.	1-12				
	·					
	i i i i i i i i i i i i i i i i i i i					
	•					
ł						
		}				
	• •					
)						
Ì		].				
ļ						
İ	·					

Form PCT/ISA/210 (continuation of second sheet) (July 1998)\*

SDOCID: <WO\_\_\_\_\_0168929A1\_!\_>

#### INTERNATIONAL SEARCH REPORT

International application No. PCT/US01/07525

A. CLASSIFICATION OF SUBJECT MATTER: IPC (7): C22C 38/08, 38/18, 38/20, 38/22, 38/28, 38/38, 38/40, 38/42, 38/44, 38/50, 38/58

Form PCT/ISA/210 (extra sheet) (July 1998)\*

\SDOCID: <WO\_\_\_\_\_0168929A1\_I\_>



## **Patent Abstracts of Japan**

**PUBLICATION NUMBER** 

11293412

**PUBLICATION DATE** 

26-10-99

APPLICATION DATE

08-04-98

APPLICATION NUMBER

10096385

APPLICANT: PACIFIC METALS CO LTD;

INVENTOR: HIRAI MASAZUMI;


INT.CL.

C22C 38/00 C22C 38/40 C22C 38/58

TITLE

**AUSTENITIC STAINLESS STEEL** 

**EXCELLENT-IN HOT WORKABILITY** 



ABSTRACT:

PROBLEM TO BE SOLVED: To provide an austenitic stainless steel free from the generation of working crack flows and streak flows in a hot rolling at high yield and at a low cost.

SOLUTION: In austenitic stainless steel having a compsn. contg., by weight, ≤0.2% C, 0.1 to 2% Si, 0.3 to 3% Mn, ≤0.04% P, 15 to 30% Cr, 3 to 30% Ni, 0.01 to 0.3% N, ≤0.003% S, ≤0.007% O and 0.002 to 0.05% Al, furthermore contg., at need, one or ≥ two kinds among ≤4% Mo, ≤4% Cu, ≤2% Nb and ≤2% Ti, and the balance Fe with inevitable impurity components, and in which Ca and Mg in which  $\delta$  calculated by Creq=(Cr%)+1.5(Si%)+(Mo%)+0.5(Nb%), Nieq=(Ni%)+30(C%+N%)+0.5(Mn%) and  $\delta$ %=-0.0816(Creq)<sup>2</sup>+5.975(Creq)-3.786(Nieq)+0.0587(Creq).(Nieq)-46.23 is regulated to ≤3% or ≤7%, Ca and Mg in which the value of (Mg%/Ca%) is regulated to ≤1 is the ranges of 0.0005 to 0.005% Ca and 0.0005 to 0.003% Mg are jointly used.

COPYRIGHT: (C)1999,JPO